

Huawei.H35-912.v2022-03-09.q58

Exam Code:	H35-912
Exam Name:	Huawei Certified Specialist - Data Center and Network Equipment Hardware Installation (Written)
Certification Provider:	Huawei
Free Question Number:	58
Version:	v2022-03-09
# of views:	1670
# of Questions views:	580
https://www.exam-tests.com/H35-912-exam/Huawei.H35-912.v2022-03-09.q58.html	

NEW QUESTION: 1

What is the input voltage of the MA5633? (Multiple choice)

- A. 48V AC
- B. 60V AC
- C. 48V DC
- D. 220V AC

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 2

Operation of electrical equipment must be authorized, qualified and competent.

- A. True
- B. False

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 3

Which of the following front-end interface card types are supported by the V3 series storage products? (Multiple Choice)

- A. iSCSI interface card
- B. 12Gb SAS interface card
- C. SmartIO interface card
- D. 8Gb FC interface card

Answer: A,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 4

About V3 storage product BBU redundancy configuration, which of the following is incorrect?

- A. 5500V3, BBU1+1
- B. 6800V3, BBU3+1
- C. 5600V3, BBU2+1
- D. 5800V3, BBU2+1

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 5

Which of the the following about the standard procedures of MA5800 is incorrect?

- A. Need to organize tools and clean up the site after installation
- B. No hardware quality check is required after installation
- C. After the cable is installed, it needs to be labeled.
- D. Install the cabinet first, then install the chassis

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 6

All new partners must first interview the corresponding project manager and product line technical leader before entering the area, and sign the safety production commitment letter, the network safety behavior red line commitment letter, and receive the supervision certificate before entering the area, new employees do not allow to operate the existing network equipment.

- A. True
- B. False

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 7

Which of the following is the general cabinet power-on procedure?

- A. Cabinet input power distribution switch closed -> single board switch closed -> chassis module power switch closed
- B. Chassis module power switch closed -> cabinet input power distribution switch closed -> single board switch closed.
- C. Single board switch closed -> chassis module power switch closed -> cabinet input power distribution switch closed
- D. Cabinet input power distribution switch closed -> chassis module power switch closed -> single board switch closed

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 8

What are the common access methods for access networks? (Multiple choice)

- A. Fiber access

- B. Cable access
- C. Power access
- D. Copper wire access

Answer: A,B,D ([LEAVE A REPLY](#))

NEW QUESTION: 9

What scene does the light cat ONT belong to?

- A. FTTC
- B. FTTD
- C. FTTH
- D. FTTB

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 10

The "High Risk Operation Plan" can be implemented at any time after being reviewed and approved by the technical representative of the customer and the representative office.

- A. False
- B. True

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 11

Which of the following insert frame are not ETSI insert frame types? (Multiple choice)

- A. MA5800-X15 insert frame
- B. MA5683T insert frame
- C. MA5800-X17 insert frame
- D. 21-inch frame MA5680T

Answer: A,B ([LEAVE A REPLY](#))

NEW QUESTION: 12

Which of the following devices need to press the power button when powering up?
(Multiple choice)

- A. RH2288 V3
- B. High-density disk enclosure
- C. 3U controller
- D. 2U disk enclosure

Answer: A,C ([LEAVE A REPLY](#))

NEW QUESTION: 13

Which of the following should be applied to the rope when manually hoisting?

- A. Do not allow jerk, emergency stop, flashing, etc.
- B. Allowing jerk, emergency stop, flashing, etc.

C. Allowing jerk, emergency stop, flashing, etc. in the case of power assurance

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 14

Which of the following are typical products for copper wire access? (Multiple choice)

A. MSAN

B. OLT

C. DSL terminal

D. DSLAM

Answer: A,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 15

Which one is not a typical product for copper access?

A. DSL terminal: such as HG630

B. DSLAM: such as MA5600

C. MSAN: such as UA5000

D. ONT: such as HG8145C

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 16

The power cable and ground wire may not use the entire copper core material, and there may be a joint in the middle.

A. True

B. False

Answer: B ([LEAVE A REPLY](#))

Valid H35-912 Dumps shared by BraindumpsPass.com for Helping Passing H35-912 Exam! BraindumpsPass.com now offer the **newest H35-912 exam dumps**, the BraindumpsPass.com H35-912 exam **questions have been updated** and **answers have been corrected** get the **newest** BraindumpsPass.com H35-912 dumps with Test Engine here: <https://www.braindumpsPASS.com/Huawei/H35-912-practice-exam-dumps.html> (175 Q&As Dumps, **40%OFF** Special Discount: **Exam-Tests**)

NEW QUESTION: 17

The EPW3000-12A is an E9000 AC power module that supports 100V AC~ 240V AC input. The E9000 does not support DC power input.

A. False

B. True

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 18

For the inspection of PPE, it only needs to be carried out at the site, and it is not necessary to check before departure.

- A. False
- B. True

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 19

Which of the following is the correct order to install the cabinet?

- A. Position the cabinet -> Fix the cabinet -> place the cabinet -> level the cabinet
- B. Place the cabinet -> Position the cabinet -> Fix the cabinet -> Level the cabinet
- C. Place the cabinet -> Fix the cabinet -> Position the cabinet -> Level the cabinet
- D. Position the cabinet -> place the cabinet -> Fix the cabinet -> level the cabinet

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 20

When entering the central computer room for "high-risk operation", which of the following actions should be followed? (Multiple Choice)

- A. Always check and confirm the network operation status in the final stage before entering the "high-risk operation" implementation.
- B. In the implementation of "high-risk operations", be sure to make detailed records of each key data operation at each step.
- C. After the "high-risk operation" is completed, the customer must be reminded to modify the network management password in time.
- D. Always keep the cybersecurity attitude of "as thin as ice"
- E. Every carriage return after entering the engine room should be treated as "high-risk operation"
- F. You can use the "super user" you know to log in to the customer network management system for data operation.

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 21

When the V3 storage uses DC power, connect the OT terminal of the black cable to the RTN (+) terminal and the OT terminal of the blue cable to the NEG (-) terminal.

- A. True
- B. False

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 22

If the data is improperly operated and the network construction takes place, it can be processed separately, and the relevant personnel will be informed after the network is completely restored.

A. False

B. True

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 23

How many 3.5-inch business hard drives (SATA) does the FusionStorage capacity storage server support?

A. 12

B. 36

C. 25

D. 75

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 24

Regarding the seat belt on the car, which one is the correct statement?

A. When you drive, be sure to fasten your seat belt. You don't have to take a ride.

B. When you drive or ride, please fasten your seat belt

C. When driving slowly, you don't have to wear a seat belt.

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 25

Which is correct about the operation of live equipment and circuits?

A. Powerful operation requires qualified personnel to perform, weak power does not need

B. Everyone can operate live equipment and circuits as long as they are insulated.

C. Operation of live equipment and circuits can only be carried out by personnel with relevant qualifications

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 26

Server survey includes two scenarios, one for determining the configuration of the BoQ for the pre-sales phase and for the supply chain, and the other for the detailed installation for hardware installation.

A. False

B. True

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 27

The CH220/CH221 compute node performs IO expansion on the basis of the CH121 compute node, and supports up to four PCIe cards in full-width slots.

A. False

B. True

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 28

How many half-width slots does the E9000 support?

A. 8

B. 16

C. 10

D. 24

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 29

Which of the following methods does not power on the server?

A. Power on the server by pressing the front panel power switch button

B. Power on the server through the iBMC command line.

C. Power on the server by pressing the UID button on the front panel

D. Power on the server through the interface provided by the iBMC web interface.

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 30

FTTB refers to fiber to the roadside.

A. True

B. False

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 31

There must be no connectors in the middle of the protective ground wire. It is strictly forbidden to install switches or fuses on the protective earth wire.

A. True

B. False

Answer: A ([LEAVE A REPLY](#))

Valid H35-912 Dumps shared by BraindumpsPass.com for Helping Passing H35-912 Exam! BraindumpsPass.com now offer the **newest H35-912 exam dumps**, the BraindumpsPass.com H35-912 exam **questions have been updated** and **answers have been corrected** get the **newest** BraindumpsPass.com H35-912 dumps with Test

Engine here: <https://www.braindumps.com/Huawei/H35-912-practice-exam-dumps.html> (175 Q&As Dumps, **40%OFF** Special Discount: **Exam-Tests**)

NEW QUESTION: 32

If the violation involves multiple aggravating standards, the penalty will be imposed at the specified level.

- A. True
- B. False

Answer: (SHOW ANSWER)

NEW QUESTION: 33

Which are the correct statements about the cabinet? (Multiple choice)

- A. IEC cabinet supports 21-inch equipment
- B. ETSI cabinet supports 21-inch equipment
- C. IEC cabinet supports 19-inch equipment
- D. ETSI cabinet supports 19-inch equipment

Answer: B,C (LEAVE A REPLY)

NEW QUESTION: 34

Which of the following is the work done during the verification phase after "high-risk operation"?

- A. Network test verification
- B. Confirmation of project operation completion
- C. Confirm the operation board
- D. Recording of major operational records

Answer: A (LEAVE A REPLY)

NEW QUESTION: 35

The power cord of the 3000KW AC power module can be plugged into the 2000KW socket.

- A. True
- B. False

Answer: B (LEAVE A REPLY)

NEW QUESTION: 36

Regarding the OLT chassis, which statement is incorrect?

- A. The slots 1-7 and 10-17 of the MA5800-X15 are service slots.
- B. The main control board of the MA5800-X17 is in slots 9 and 10.
- C. MA5680T subrack supports 16 service slots.
- D. MA5683T subrack supports 8 service slots.

Answer: (SHOW ANSWER)

NEW QUESTION: 37

What is the range of copper wire recommended by Vectoring/SuperVector/G.fast in the FTTC scenario?

- A. 5Km or more
- B. 1Km~3Km
- C. 100m~500m
- D. 500m~1Km

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 38

What are the requirements for construction in hazardous areas? (Multiple choice)

- A. Erection of warning signs and enclosure isolation measures
- B. Provide appropriate safety protection for personnel in hazardous area construction, using special safe working tools
- C. In the construction of hazardous areas, emergency measures and safety measures must be taken

Answer: ([SHOW ANSWER](#)**)**

NEW QUESTION: 39

Which of the following should be noted when handling goods? (Multiple choice)

- A. Unobstructed passage
- B. Can't drag directly on the ground
- C. Sufficient staff
- D. Rigging is secure

Answer: A,B,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 40

Which of the following is not included in the hard-loaded standard procedure of the MA5800?

- A. Install the power and ground wires
- B. Install the machine frame
- C. Software commissioning
- D. Installing and tying the fiber

Answer: ([SHOW ANSWER](#)**)**

NEW QUESTION: 41

What is the correct statement about the layout specification of the OceanStor 18000 V3 storage cable? (Multiple Choice)

- A. The bending radius of the fiber placement should not exceed 50mm
- B. When the cable is laid, it should be straightened out without bending

- C. The power cable and ground wire should be smooth at the turn.
- D. The wire diameter of the power cable and ground wire of the equipment should meet the power distribution requirements of the equipment.

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 42

What is the management requirement for the lower (non-safe area) of aerial work?

- A. It is strictly forbidden to walk or perform other work
- B. Allow people to walk or do other work
- C. Personnel can move around or perform other work with a reminder

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 43

Which of the following are in the scope of the MA5800 box series hardware quality standards? (Multiple Choice)

- A. Power and grounding standards
- B. Cabinet frame standard
- C. Signal cable standard
- D. Integrated commissioning standards

Answer: A,B,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 44

Which of the following are typical FTTx scene types? (Multiple choice)

- A. D-CCAP
- B. FTTH
- C. FTTC
- D. FTTB

Answer: B,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 45

What cable and grounding bar do I need to connect to the MA5800?

- A. DC power cord
- B. Upstream fiber
- C. Protective ground wire
- D. Downstream fiber

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 46

E9000 2.5KW DC power module supports 240V HVDC high voltage DC input.

- A. True
- B. False

Answer: B ([LEAVE A REPLY](#))

Valid H35-912 Dumps shared by BraindumpsPass.com for Helping Passing H35-912 Exam! BraindumpsPass.com now offer the **newest H35-912 exam dumps**, the BraindumpsPass.com H35-912 exam **questions have been updated** and **answers have been corrected** get the **newest** BraindumpsPass.com H35-912 dumps with Test Engine here: <https://www.braindumpsPASS.com/Huawei/H35-912-practice-exam-dumps.html> (175 Q&As Dumps, **40%OFF** Special Discount: **Exam-Tests**)

NEW QUESTION: 47

The cabinet with the E9000 installed has a minimum depth of 1.2 meters.

- A. False
- B. True

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 48

What should be prepared for the preparation of first aid?

- A. Emergency rescue phone number, emergency location and map
- B. Office location
- C. Home address

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 49

When the MA5800 uplink fiber connection is connected, which statements are correct?
(Multiple Choice)

- A. Upstream adopts SC type fiber
- B. One end is connected to the uplink port, and the other end is connected to the corresponding optical port of the ODF frame.
- C. Fiber needs to be tied
- D. The fiber needs to be placed in the bellows at the top of the cabinet.

Answer: B,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 50

Huawei's equipment is maintained by Huawei. When we perform engineering quality inspection, we can enter the equipment room and directly operate Huawei equipment.

- A. False
- B. True

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 51

What is the correct treatment method for snakes found in the site?

- A. Drive the snake to a distance
- B. Notification of wildlife protection related organizations
- C. Direct death

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 52

Regarding the aerial work PPE, which one is the correct statement?

- A. When working at height, the tower worker can choose any personal protective equipment that he likes to wear.
- B. All workers must wear appropriate personal protective equipment when working at height
- C. When working at height, personal protective equipment may not be provided for skilled tower workers.

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 53

The work on the tower only needs to hang the double hook safety rope and does not need the positioning rope to position the waist.

- A. True
- B. False

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 54

How many hard disks in each high-density disk enclosure of OceanStor V3 store?

- A. 100
- B. 25
- C. 12
- D. 75

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 55

What are included in the electrical safety requirements? (Multiple Choice)

- A. Damaged power supply components must be replaced in time.
- B. Do not overload the power supply.
- C. Do not place the power cord on the ground.

Answer: A,B,C ([LEAVE A REPLY](#))

NEW QUESTION: 56

What are the correct statements about the seat belt of the vehicle? (Multiple Choice)

- A. Driver training includes how to use seat belts
- B. Seat belt inspection as part of routine maintenance
- C. All company vehicles need to be equipped with seat belts

Answer: A,B,C ([LEAVE A REPLY](#))

NEW QUESTION: 57

What services can MSO provide? (Multiple choice)

- A. Radio and television, including analog, digital, etc.
- B. Voice Service (VOIP)
- C. Broadband services, including HSI, Wifi, etc.
- D. Power introduction, that is, the supply of electricity

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 58

Which of the following statements about the up-and-down about PON technology is correct?

- A. PON technology data uplink uses broadcast
- B. PON technology uplink adopted wavelength is 1490nm
- C. PON technology downlink adopted wavelength is 1310nm.
- D. PON technology data downlink uses broadcast

Answer: D ([LEAVE A REPLY](#))

Valid H35-912 Dumps shared by BraindumpsPass.com for Helping Passing H35-912 Exam! BraindumpsPass.com now offer the **newest H35-912 exam dumps**, the BraindumpsPass.com H35-912 exam **questions have been updated** and **answers have been corrected** get the **newest** BraindumpsPass.com H35-912 dumps with Test Engine here: <https://www.braindumpsPass.com/Huawei/H35-912-practice-exam-dumps.html> (175 Q&As Dumps, **40%OFF** Special Discount: **Exam-Tests**)